

अखिल भारतीय आयुर्विज्ञान संस्थान

अंसारी नगर, नई दिल्ली-110029

All India Institute of Medical Sciences

ANSARI NAGAR, NEW DELHI-110029

No. Engg./ *elect/RF no 17/11-12*

Dated the *28-5-11* 200.....

NOTICE INVITING QUOTATIONS

SHORT NOTICE

Quotations are invited by Post per bearer for the supply of the following materials. The quotations should be addressed to the Director, A.I.I.M.S., New Delhi and should reach him on or before 200..... at the latest in sealed envelop superscribe Quotations for *M.A. Bailor at C.S.S Deptt. at A.I.I.M.S. Delhi (sh. Repl. of worn out m.c.B)*

All quotations should be inclusive of Sales Tax and other Local Taxes and the minimum time which the supply can be effected. Quotations should be type written or in ink. Quotation written with a pencil will not be considered. The quotation will be opened at *3.30* P.M. on *3-6-11* 200..... by the Executive Engineer / Asstt. Engineer, A.I.I.M.S., in the Office.

DESCRIPTION OF ARTICLES

Est. Cost: - *₹ 69,142*

Item No.	Description of Articles	Quantity	Rates in fig. & words	Unit	Amount
----------	-------------------------	----------	-----------------------	------	--------

As per schedule attached

Total

S. K Rastogi
(S. K Rastogi)
Executive Engg (Elect)

I / We hereby tender for the executive supply of the work / materials specified in the above written memorandum at% (Rupees percent) only above / below the rates mentioned. I / We also hereby agree to complete with work / supply within days from the date of receipt order to commence.

SIGNATURE OF CONTRACTOR / SUPPLIER

UNDER HIS / THEIR SEAL

SCHEDULE OF WORK

Name of Work: M/O Boilers at CSSDeptt at AIIMS, New Delhi.

(SH: Replacement of worn-out MCCB)

No.	Description of Items	Qty	Rate	Unit	Amount
1.	Dismantling the worn-out existing FP MCCB & P/F the new FP, 200Amp MCCB, 25 KA, 415V, 50Hz Adjustable Thermal & Fixed Magnetic Setting Type i/c connection & testing etc. as required. Make: Havell's. (All the dismantled material are to be retained by the firm as buy back basis)	2Nos		each	
2.	Dismantling the worn-out existing TP MCCB & P/F the new TP, 630Amp MCCB, 50 KA, 415V, 50Hz Adjustable Type i/c connection & testing etc. as required. Make: GE. (All the dismantled material are to be retained by the firm as buy back basis)	1No		each	
3.	Supplying of following size PVC insulated, PVC sheathed, armoured aluminium conductor cable, 1.1KV grade conforming to IS: 1554(Part-I) amended up to date as reqd. Make: Plaza/Havell's/Kalinga/Sky tone with ISI marked.				
(a)	3 ^{1/2} X400 sqmm	4mtrs		metre	
4.	Laying and fixing of one number PVC insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1KV grade of size exceeding 120sq.mm but not exceeding 400sq.mm on surface as required.	4mt		meter	
5.	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with the existing surface / recessed conduit/sub main wiring / cable as required.	8mt		metre	
6.	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1KV grade as required.				
(a)	3 ^{1/2} X 400 sqmm	2nos		each	

7.	Replacement of following parts in the existing control panel of Electrode Steam Boiler i/c connection and testing etc. as required of BCH make. (All the dismantled material are to be retained by the firm as buy back basis)				
(a)	16Amp Contactor, 4P, Cat: COON	1no		each	
(b)	Timer as per sample	1no		each	


 (S.K. Rastogi)
 Executive Engineer (E)